

13/01676

# Detail of fixing points to mid pivot steady bar

SUCKTON BOROUGH COUNCIL  
PLANNING  
23 JAN 2013  
DATE RECEIVED

Rawl type bolts drilled into stonework 14mm holes to approx 60mm deep

It will be necessary to fix these brackets at approximately 2.0m intervals across the full width of the building facade. They will vary in depth to take into account the variations of the building at each fixing point.

Galvanized steel strap

SBC0003

FRONT OF BUILDING

Facade stonework

Printed me:  
graphic

