Proposed Elevations

① Proposed South Elevation

EXISTING SCHOOL BUILDING · NEW LINK CORRIDOR · NEW EXTENSION

② Proposed North Elevation

NEW EXTENSION · EXISTING SCHOOL BUILDING · MAIN ENTRANCE · REMODELLED ENTRANCE AND STAFF AREAS · EXISTING NURSERY · NEW CANOPY

③ Proposed East Elevation

EXISTING SCHOOL BUILDING (in the background) · NEW EXTENSION

④ Proposed West Elevation

REMODELLED STAFF AREAS · NEW CANOPY · EXISTING SCHOOL BUILDING

⑤ Proposed West Elevation of the Main Extension

NEW EXTENSION

KEY:

- Facing Brick, type TBC
- Vertical Timber Cladding
- Through colour render, white
- Through colour render, white, on existing brickwork wall
- Aluminium doors and windows, polyester powder coated, colour dark grey, RAL ref. TBC
- Existing window replaced with new aluminium window (as item...)
- New aluminium window (as item 4) in existing wall
- Aluminium fascias, copings, gutters and rainwater downpipes, polyester powder coated, colour dark grey, RAL ref. TBC
- PVC membrane roof with standing seam feature, colour lead grey
- Timber clad steel columns
- Natural air vents, polyester powder coated, colour dark grey, ref. TBC
- Glazed entrance canopy
- Proprietary new canopy to nursery
- New 2.1m high weld-mesh security fence, colour TBC
- Existing bin store moved to new location, painted to match new fence

Key Plan (1:500)